Abstract estimate of quantities for restoring Basavenahalli Doddakere (Minor tank) Reg. No. 59 in Honnali Taluk.

No.	Items of works	Unit	Quantity
	BUND R. L. 56·50. TOP WIDTH 4½ FEET.		
1	Clearing jungle over the bund and cutting grips ..	Lump sum	
2	Earthwork excavating, carrying, watering and tamping.	Yards	3,035
3	Turfing front and rear slopes	Sqr.	350·00
4	Providing Index stones with bed slabs including dressing and fixing.	No.	26
5	Providing Index stones with bed slabs including dressing and fixing.	„	26
6	Providing Register No. stone including painting, dressing and fixing.	„	1
7	Providing B. M. stones including painting, dressing and fixing.	„	2
8	Resting the damaged revetment with new jelly backing and wedging.	Lump sum	
	SLUICE AT C. S. 8 R. L. 45·50.		
1	Earthwork excavation	Yds.	67
2	Filling in earth with consolidation	„	59
3	Stone jelly concrete in surki mortar ...	C.ft.	207
4	Size stone in surki mortar	„	253
5	Burntstone slabs 3" to 4" thick dressed and fixed ...	Sqr. ft.	62
6	Pointing with surki mortar	Sqr.	3·00
7	Cutting holes in orifice slabs	Lump sum	
8	C. I. pipes 7" diameter including Railway freight, cost and carting to work spot and fixing in cement.	R.ft.	36
9	Teakwood plug with iron rod including locking arrangements, etc., complete.	No.	1
	WASTEWEIR LEFT 102 FT. LONG AT R. L. 51·00.		
1	Earthwork	C.yd.	93
2	Stone jelly concrete in surki mortar ..	C.ft.	333
3	Size stone in surki mortar	„	887
4	Burnt stone slabs 3" to 4" thick dressed and fixed ...	S.ft.	172
5	Pointing with surki mortar .. .	Sqr.	3·00
6	Rough stone work new .. .	C.yds..	115

R. L. STEELE,
Executive Engineer.

CHITALDRUG DISTRICT.

Notification dated 10th May 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 15th June 1930, for constructing Veterinary Dispensary at Davangere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 400 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Veterinary Dispensary at Davangere, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender of to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7 The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for constructing Veterinary Dispensary at Davangere.

No.	Items of work	Unit	Quantity
1	Earthwork excavation and filling in basement	C.yds.	155
2	Concrete in mortar	C.ft.	1,030
3	Stone in clay foundation	„	3,541
4	Do basement	„	513
5	Brick in mud	„	5,506
6	Burnt stone slabs 4" to 6" well dressed and fixed	S.ft.	122
7	Do slabs 6" neatly dressed and fixed for steps ...	„	248
8	Burnt brick in mortar	C.ft.	550
9	Cut stone pillars 9" x 9" neatly dressed and fixed with base and capital, etc.	No.	4
10	Burnt stone slab pillars 6" neatly dressed and fixed including cutting groves.	S.ft.	69
11	Teakwood doors pannelled with frame, hinges, etc , complete ...	„	137
12	Teakwood battened door with frame, hinges, etc., complete ...	„	45½
13	Do windows with frame battened shutters including ¾" iron bars, hinges, hooks, etc.	„	24
14	Do windows with frame and iron bars ¾" including pannelled shutters outside and glazed shutters inside with hooks and rings, etc., complete.	„	60
15	Teakwood work wrought and put up with wood oiling ...	„	181
16	Roofing with 1st class Mangalore tiles on teak reepers, etc., complete.	Sqr.	29
17	Flooring with kadapa slabs 1½" over 3" concrete bed including cement pointing.	„	9·94
18	Plastering with mortar	„	61·91
19	Chunnam plastering rough	„	66·84
20	White washing 2 coats	„	61·91
21	Painting to doors and windows with blue silicate paint 2 coats ...	„	6·22
22	Pointing to basement for cattle shed	Lump	sum
23	Pointing in lime mortar with lining	Sqr.	17·85
24	Do with cement	„	1·78
25	Ornamental eave board 9" wide	R.ft.	262
26	Teakwood finials including fixing and painting, etc. ...	No.	4
27	Tarring eaves, bressummers, etc.	Lump	sum
28	Flooring with gravel including water and tamping, etc., complete	C.yds.	11
29	Thick mortar bonds over roof	R.ft.	306
30	Coping with burnt brick in clay and chunnam plastering including pillasters.	„	1,010
31	Caps and plain cornice to gate pillars	No.	4
32	Providing teakwood gate with 3" x 4" frames and 2" x 1" reepers including painting, etc.	S.ft.	120
33	Clearing site and levelling ground and other unforeseen works ...	Lump	sum

A. TANDONI RAO,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS,

GOVERNMENT GARDENS DEPARTMENT, LAL-BAGH, BANGALORE.

Notice.

Notice is hereby given that separate sealed tenders from approved firms and merchants for articles noted below, will be received till 2 P.M., on Monday the 2nd June 1930, by the Superintendent, Government Gardens, Bangalore, for the supply by contract of contingent articles, pots and manure for the Parks and Gardens at Mysore from 1st July 1930 to 30th June 1931 both days inclusive.